

Lubbock or Leave It

Bringing the Canyon Lakes Interceptor Back to Life

Justin Reeves, PE
Grace Wike, PE



Lockwood, Andrews
& Newnam, Inc.
A LEO A DALY COMPANY



The Canyon Lakes Interceptor was surcharging and needed upgrades

The history


Diagnosing the problem

Developing the solution

Phased implementation

Results

The interceptor was nearing 50 years old and in need of upgrades



Multiple project constraints required a unique solution



Prehistoric settlements



Agriculture Museum



1970 Tornado backfill



Joyland Amusement Park




Lubbock Lake Landmark



Wind Power Museum

Waters of the US surround the project work site




A condition assessment was conducted to understand the system

- CCTV (37,383 of 45,960 LF)
- Ultrasonic thickness testing



- Manhole inspection (85 MHs)

CCTV showed several segments of metallic pipe



We inspected 10 aerial crossings and found 8 needed replacement



Steel carrier pipe (2)
Ductile iron carrier pipe (7)
PVC carrier in steel casing (1)



The assessment identified three major categories of problems




The first major category:

Isolated condition defects

- Collapsed pipe
- Offset joints
- Thinning pipe wall
- Tuberculation

Several rehab methods were used to address the condition of the interceptor

19 Road / RR / Creek
Xings metallic pipe
replacements




Heavy Clean / CCTV
remaining segments



4,400 LF CIPP MH to MH

We found an opportunity to eliminate a siphon




Construction uncovered a major pipe collapse




The second finding was deteriorated manholes



The third major diagnosis was an overall lack of capacity



To address the additional capacity we identified a new WWTP flow diversion



Finally, our PER also addressed maintenance

- Recommendations:
 - Improve manhole spacing
 - Provide manholes at all bends

Preliminary Engineering Report

Canyon Lakes Sanitary Sewer Interceptor Rehabilitation

October 2014




lan Lockwood, Andrews
& Newnam, Inc.
A LEO A DALY COMPANY

 city of
lubbock
TEXAS

The final solution included some impressive metrics

Auger Boring	12 bores / 2,000 LF
CIPP MH to MH (estimated)	4,400 LF
Open Cut	4,000 LF
Heavy Cleaning	6,000 LF
Aerial Crossings	8 segments / 1,100 LF
New Manhole	35 (Primarily to improve spacing)
Manhole Rehab	70

Balancing the work



Phasing the Work | Hydraulics

Goal -> Maximize impact early

Phase 1 (FY16): Remove sources of blockage (new pipe)

Phase 2 (FY17): Remove sources of blockage (cleaning)

Phase 3 (FY17): Pipeline point repair and rehabilitation

Phase 4 (FY18): Manhole rehabilitation

Phasing the Work | Funding

Goal -> Work within annual budgets

Phase 1 (FY16): Replace metal carrier pipe

Phase 2 (FY17): Clean heavy tuberculation

Phase 3 (FY17): Pipeline point repair and rehabilitation

Phase 4 (FY18): Manhole rehabilitation

Phasing the Work | Construction

Goal -> Minimize cost with packaging

Phase 1 (FY16): Bored crossings of all roadways

Phase 2 (FY17): Cleaning and CCTV assessment

Phase 3 (FY17): Trenchless rehabilitation (CIPP)

Phase 4 (FY18): Manhole rehabilitation

Approach Results

Parameter	Original (Replacement)	Proposed (Phased Rehab)	Reduction
Length of Improvements (LF)	43,600	12,100	72%
Land Disturbance (AC)	27	4	85%
Archeological Disturbance (AC)	22	3	86%
Construction Cost (\$)	\$ 18,500,000	\$ 14,200,000	23%
Construction Duration (Days)	440	320	27%

TSPE South Plains 2015 Trailblazer Award

Current Project Status

Phase 1 (Metal Pipe | Road Crossings)

- In construction (\$5,300,000 Contract Value)

Phase 2 (Cleaning | Assessment)

- Advertising for bid (\$1,200,000 Engineer's OPCC)

Phase 3 (Pipeline Rehabilitation)

- In design
- Anticipated bid fall 2017 (\$7,000,000 Engineer's OPCC)

Phase 4 (Manhole Rehabilitation | Construction)

- Anticipated bid ~fall 2017 (\$1,000,000 Engineer's OPCC)