

Underground Construction Technology | January 28-30, 2020 | Fort Worth, TX

Colsman Tunnel Project

Location: Centennial Colorado

Owner: Southgate Sanitation District

Owner Rep: Burns & McDonnell Engineering

Prime Contractor: Garney Construction

Design Engineer: Dewberry Engineering

Consulting Engineer: Shannon & Wilson

Trenchless Slip-Line Contractor: Global Underground Corp


HDPE Provider: ISCO Industries

HDPE Manufacturer: WL Plastics

Underground Construction Technology | January 28-30, 2020 | Fort Worth, TX

Colsman Tunnel Non-Interruptible Wastewater Flow

- > Length: 7,632 Lineal Feet (LF)
- **→** Hand Dug 1976-1978 thru Hard Claystone
- > Tunnel Height and Width Inconsistent
- > Tunnel Floor Slope ~ 0.36%
- **➤ Maximum Cover Depth 95 feet**
- Wire Mesh/Shotcrete/Coal Tar Epoxy Lining










Avg Weekday Flows = 5,000 gpm Peak Weekday Flows = 7,700 gpm



Underground Construction Technology | January 28-30, 2020 | Fort Worth, TX



Defects
Verified
by
Floating
Camera



Multi-Sensor Robotic Inspection Float Camera = Hi-Tech




FIGURE 14 - DEFECT CODING	DISTANCE (FT)
	AT/FROM
LINING FAILURE DETACHED (LFD)	2
LINING FAILURE DETACHED (LFD)	2
SURFACE SPALLING (SSS)	265
SURFACE SPALLING (SSS)	265
TAP BREAK-IN ACTIVE (TBA)	4759
SURFACE AGGREGATE VISIBLE (SAV)	5313
INFILTRATION WEEPER (IW)	5618
SURFACE AGGREGATE VISIBLE (SAV)	5873
SURFACE AGGREGATE VISIBLE (SAV)	7502

HDR Engineering, Inc.

4'-3"

|=n._m=n|=||= |||=||=||=||=||=

Hard Claystone

closed-circuit television (CCTV) survey data








Slip-Line Method Selected HDD Rig to Pull 7,632 LF of 48" SDR 13.5 IPS weighing over 1,680,000 pounds thru Tunnel







Underground Construction Technology | January 28-30, 2020 | Fort Worth, TX

Material Data Set

HDPE Pipe

❖Length = 50 ft

- **❖Butt Fusion ASTM F-3183**
- **❖Wt** = 218 lbs/ft on avg.
- **❖Total Wt = 1,680,842 lbs**

Drill Stem Pipe

- ❖Length Avg = 31.6 ft
- OD = 6-5/8"
- **❖**Tool Joint OD = 8-1/2"
- ❖Make-up Torque = 58,840 ft/lbs
- ♦ Wt = 38 lbs/ft on average
- ❖Total Wt = 297,312 lbs (7824LF)


Underground Construction Technology | January 28-30, 2020 | Fort Worth, TX

Good Questions NEED Great Answers:


- How do you get 7,700 Feet of Drill Stem thru a Tunnel without Damage to Either?
- **❖** What are the expected Pull-Back Forces?
- What Type of Pull-Head is Needed?
- **❖** What Size Drill Rig is Needed?
- What Anchorage is Required to keep the Drill Rig from pulling itself into the Tunnel?
- Identify Weakest Link and Strengthen!

Underground Construction Technology | January 28-30, 2020 | Fort Worth, TX

Global Underground used our American Auger DD-440T with a



DD-440T with a DD-1100RS On-Standby




Underground Construction Technology | January 28-30, 2020 | Fort Worth, TX

Calculated Max Pull Force


W12x170

Drill Rig Foot Anchor typ.



= 660,227 lbs

Match
Anchor Pad Design
& Drill Rig Capacity






East Portal Drill Rig Set-Up

Underground Construction Technology | January 28-30, 2020 | Fort Worth, TX









ACTION PLAN:

Winch over 297,000 lbs of Drill Stem Thru Tunnel


How?


Place a 120,000 lb Capicity Winch at one End w/Modular Sheave Roller System keeping the Cable from hitting the Roof


Float a Bouy Tied to 1/4" Rope Tied to 1/2" Poly/Steel Rope Connected to 9/16" Steel Cable Connected to 1-1/4" Steel Cable

Use the 1-1/4" Steel Cable Connected to 58T Swivel Connected to 16" dia. Pig Connected to the Drill Stem


Then Just REEL it IN...














Design/Build/Install Modular Sheave Roller System in West Vault





Looking Into Tunnel






"Buoy Watch"









Buoy w/Beacon Buzzer tied to 8000 LF of 1/4" Rope Set Adrift and Captured ~ 2 Hours Later




Encapsulate Shackles in PIGS & Spool-Out Down Stream










150' Unsupported Drill Stem Length







The Underground

Preparing to Winch Drill Stem thru Tunnel




















Safe Pull Force Analysis

Underground Construction Technology | January 28-30, 2020 | Fort Worth, TX

3 - HDPE Components




Design/Build Reinforced Pull-Head Assembly Pull Force Gained = 163,730 lbs.






Global Underground Fabricated HDPE Pull-Head







Now to
Connect
Pull-Head to
Drill Stem
and Ease it
into the
Tunnel,



West Portal Vault



Very Carefully!



Rocky Mountain Winter = Controlled Fusion Environment












Claustrophobia?


50' Inside






Pre-Test:
Samples
from 12,
3, 6 & 9
o'clock
positions
Planed
Flat to
1/4" Thick






Sample Bent at 90-degree angle

Post-Test: Visual Inspection of Combined Fusion Bead Zone









Underground Construction Technology

Due to Pipe Spiral/Rotation into Tunnel TEE is Fused at Max Angle



ISCO 48"x36"x24" Reducing Tee w/MJ adapters
Fused at Max Rotation to enter Tunnel at Vertical





Pull Back Operations effect the Tee Position





Pull-Back Forces during the Slip-Line Operations:

Max = 100,000 lbs

Average = 60,000 lbs

Final Pull = 53,000 lbs





The Pipe had Rotated at 1/8 of a Turn Clockwise over the ~ 200' into the Tunnel for Two Weeks!

100 ft Later - Rotated Straight Up

We've got 100 ft Yet to GO!

New Challenge: STOP REGROUP



Move Fusion Machine into Position





















550 Ton Brewis Swivel

? Questions?



In Memoriam: Steve McCandless
The project team would like to
recognize Steve McCandless of Garney
Construction, who passed away shortly
after completion of the tunnel lining.
His colleagues saw Steve as an
incredible person in every way and an
inspiration to many.

Robert Meadows, President
Rob Powilleit, Vice President
Eric Ensign, Chief Financial Officer
Richard Bond, PE, Project Specialist
Call: 719-471-7414
641 Winters Drive
Colorado Springs, CO 80907









